

Page 1 of 13

EXTERNAL VISUAL INSPECTION OF ELECTRICAL CONNECTORS

ESCC Basic Specification No. 2053400

Issue 2	February 2014



Document Custodian: European Space Agency - see https://escies.org



No. 2053400

ISSUE 2

PAGE 2

LEGAL DISCLAIMER AND COPYRIGHT

European Space Agency, Copyright © 2014. All rights reserved.

The European Space Agency disclaims any liability or responsibility, to any person or entity, with respect to any loss or damage caused, or alleged to be caused, directly or indirectly by the use and application of this ESCC publication.

This publication, without the prior permission of the European Space Agency and provided that it is not used for a commercial purpose, may be:

- copied in whole, in any medium, without alteration or modification.
- copied in part, in any medium, provided that the ESCC document identification, comprising the ESCC symbol, document number and document issue, is removed.



No. 2053400

ISSUE 2

PAGE 3

DOCUMENTATION CHANGE NOTICE

(Refer to https://escies.org for ESCC DCR content)

DCR No.	CHANGE DESCRIPTION
838	Specification upissued to incorporate editorial changes per DCR.



TABLE OF CONTENTS

1	SCOPE	5
2	TEST CONDITIONS	5
3	GENERAL	5
3.1	CLEANING PROCESS	6
4	CONTACTS	6
4.1	BURRS AND BULGES	6
4.2	GOLD-PLATING	7
4.3	SOLDER-PLATING	8
4.4	OTHER DEFECTS	8
5	INSERTS	9
6	HOUSING AND ACCESSORIES	10
6.1	BURRS AND BULGES	10
6.2	BRAZED PARTS (WHEN APPLICABLE)	11
6.3	PLATING	11
6.4	SOLDER-PLATING	12
6.5	OTHER DEFECTS	12
7	COMPLETE ASSEMBLIES	13



No. 2053400

ISSUE 2

1 <u>SCOPE</u>

This specification, to be read in conjunction with ESCC Basic Specification No. 20500, External Visual Inspection, specifies additional external visual inspection requirements for electrical connectors, rectangular, circular, PCB and coaxial, R.F. attenuators, loads and couplers.

NOTES:

The term "coaxial connectors" shall be understood to include: coaxial connectors, R.F. attenuators, loads and couplers.

2 TEST CONDITIONS

The inspection of a connector or contact lot shall be performed as follows:

- Naked eye: 100% for general examination.
- Binocular or stereoscopic microscope with a X6 to X10 magnification, sample size in accordance with the Table below.

Lot Size	Sampling
2 to 15	2
16 to 25	3
26 to 90	5
91 to 150	8
151 to 280	13
281 to 500	20
501 to 1200	32
1201 to 3200	50
3201 to 10000	80

In case of doubt in the interpretation of a defect, a magnification of maximum X20 is allowed.

Components being inspected using optical equipment shall be illuminated such that a particle or blemish measuring 0.0125mm in the major dimension can be detected at magnification X20.

3 <u>GENERAL</u>

A component shall be rejected if it exhibits one or more of the defects listed in the following paragraphs.

Accept or reject criteria are established in relation to functional and/or non-functional areas as applicable (N/A indicates that the criteria is not applicable):

• A functional area is one which contributes to the electrical and/or mechanical function. The letters "PID" in the text mean "Process Identification Document".

Foreign matter shall be considered as attached if it cannot be removed by the specified cleaning process.

A detachable burr is any burr that can be detached when connectors are mated or installed.



No. 2053400

ISSUE 2

3.1 CLEANING PROCESS

Cleaning of the component is only allowed as follows:


- Nominal gas blow (dry nitrogen or dry filtered air, 14N/cm²), or
- According to the process specified in the PID.

4 <u>CONTACTS</u>


4.1 BURRS AND BULGES

A burr is a rough or ragged protrusion such as is caused by a cutting tool.

A bulge is any raised material which distorts the design profile.







Bulge

Either shall be considered as a defect	Func	tional	Non-Functional	
when it:	Accepted	Rejected	Accepted	Rejected
Is greater than 0.1mm in any dimension.	-	Х	N/A	N/A
Is greater than 0.05mm on the female contact entry or on the functional area of the male contact.	-	Х	N/A	N/A
Prevents the introduction of prescribed wires.	-	х	N/A	N/A
Causes any dimension to exceed its limits.	-	Х	-	Х
Is likely to damage an element of the component (gasket).	-	Х	N/A	N/A
Is likely to be a hazard to personnel.	-	Х	-	Х



ISSUE 2

The following shall be looked for in	Functional		Non-Functional	
particular:	Accepted	Accepted Rejected		Rejected
Burr on contact retention shoulder.	-	Х	Х	-
Burr on solder pot.	N/A	N/A	Х	-
Burr obscuring more than 30% of crimp inspection hole.	N/A	N/A	-	Х
Detachable burrs.	-	Х	-	Х

4.2 <u>GOLD-PLATING</u>

All surfaces shall be free from foreign particles and contamination. There shall be no evidence of corrosion, holes, cracks and peeling. Surfaces achieved by one process or the same sequence of operations shall be of uniform appearance and colour. In addition, gold-plating is not supposed to present an appreciable change in colour according to the data of the parts defined in the PID (reference parts).

The following shall be looked for in	Func	Functional		nctional
particular and shall be deemed cause for rejection:	Accepted	Accepted Rejected		Rejected
Any scratch on plating, showing base metal or underplate.	-	Х	-	Х
Stained plating.	-	Х	Х	-
Any blister on plating.	-	Х	-	Х
Any extraneous plating residue.	-	Х	-	Х
• Dull and dark aspect at bottom of female contact or solder bucket or crimp bucket (a dull and light aspect is permitted).	-	Х	-	Х
Nodular aspect.	-	Х	Х	-
Flakes and whiskers.	-	Х	-	Х



No. 2053400

ISSUE 2

4.3 <u>SOLDER-PLATING</u>

The following shall be looked for in	Func	Functional		Non-Functional	
particular:	Accepted	Accepted Rejected		Rejected	
Incorrect distribution of solder alloy.	-	Х	N/A	N/A	
Incomplete covering or dewetting.	-	Х	N/A	N/A	
Oxidation of plating.	X(1)	-	N/A	N/A	
• Solder alloy with granular aspect.	X(1)	-	N/A	N/A	
Porosity of solder alloy.	X(1)	-	N/A	N/A	

NOTES:

1. If solderability test as per applicable Generic Specification, is acceptable.

4.4 <u>OTHER DEFECTS</u>

The following shall be looked for in	Func	Functional		Non-Functional	
particular and shall be deemed cause for rejection:	Accepted	Rejected	Accepted	Rejected	
• Bent contact. (Contacts shall be aligned on a flat area. A contact will be considered as bent if its end deviates by more than half the diameter).	-	Х	N/A	N/A	
• Deformation or dents.	-	Х	Х	-	
Trace of shock, showing base metal.	-	Х	-	Х	
Any crack on socket sleeve.	-	Х	-	Х	
• No inspection hole in crimp bucket.	N/A	N/A	-	Х	
No lead-in chamfer on female contact.	-	Х	N/A	N/A	
• No radius or cone on male contact.	-	Х	N/A	N/A	
No lead-in chamfer on crimp bucket.	N/A	N/A	-	Х	
 Machining marks on male contact, giving a degree of rugosity greater than the value specified in the PID. 	-	Х	N/A	N/A	



No. 2053400

ISSUE 2

5 <u>INSERTS</u>

	The following shall be looked for in	Func	tional	Non-Functional	
	particular:	Accepted	Rejected	Accepted	Rejected
Hard Inserts • Any break whose length exceeds 0.8mm or 50% of the distance between two adjacent holes, or hole and periphery of insert.		-	Х	N/A	N/A
	Any crack.	-	Х	-	Х
	• Moulding flash >0.25mm.	-	Х	Х	-
	Moulding flash preventing contact insertion.	-	Х	N/A	N/A
Soft Inserts	Any cut or tear.	-	Х	Х	-
PFTE Inserts	 Any tear area in interfacial zone >0.5mm². 	-	Х	N/A	N/A
•	• Any scratch >0.2mm (depth).	-	Х	Х	-
	Any crack.	-	Х	-	Х
All Inserts	 Non-homogeneous colour of one insert block (assembled elements may show different shades of colour due to different moulding lots). 	Х	-	X	-
	Any inclusion (hermetic connectors only).	-	Х	х	-
	 Foreign particles. (Accept if removed after cleaning. Otherwise, not admissible for re- submission at any time). 	-	Х	Х	-
	• Any contact cavity identification letter or symbol missing or illegible that could produce a possible error in contact location.	N/A	N/A	-	Х



6 HOUSING AND ACCESSORIES

6.1 BURRS AND BULGES

A burr is any rough or ragged protrusion such as is caused by a cutting tool.

A bulge is any raised material which distorts the design profile.

Either shall be considered as a defect	Func	tional	Non-Functional	
when it:	Accepted	Rejected	Accepted	Rejected
• Is greater than 0.2mm (0.1mm for coaxial connectors only).	-	Х	N/A	N/A
Causes any dimension to exceed its limits.	-	Х	-	х
 Is likely to damage an element of the component (gasket) or the fixture onto which the component is mounted. 	-	х	-	Х
 Is likely to be a hazard to personnel. 	-	Х	-	Х
The following shall be looked for in particular:				
Burr on thread edges.	-	Х	Х	-
Burr or bulge >0.1mm in engagement area (0.05mm on functional area of coaxial connector only.	-	х	N/A	N/A
Machining marks outside engagement area.	N/A	N/A	X	-
Machining marks, having a degree of rugosity greater than the value specified in the PID, in engagement area or on functional areas.	-	х	N/A	N/A
Detachable burr.	-	Х	-	Х





No. 2053400

ISSUE 2

6.2 BRAZED PARTS (WHEN APPLICABLE)

The following shall be looked for in	Func	tional	Non-Fu	nctional
particular and shall be deemed cause for rejection:	Accepted Rejected		Accepted	Rejected
Incorrect distribution of brazing alloy.	-	Х	Х	-





Incorrect

Correct

The following shall be looked for in	Functional		Non-Functional	
particular and shall be deemed cause for rejection:	Accepted	Rejected	Accepted	Rejected
Incomplete covering or dewetting.	-	Х	-	Х
Oxidation of plating.	-	Х	Х	-
• Brazing alloy with granular aspect.	-	Х	Х	-
Porosity of brazing alloy.	-	Х	Х	-
Hole in brazing alloy if the bottom is not visible.	-	Х	-	Х

6.3 <u>PLATING</u>

All surfaces shall be free from foreign particles and contamination. There shall be no evidence of corrosion, holes, cracks and peeling.	Functional		Non-Functional	
	Accepted	Rejected	Accepted	Rejected
Any scratch on plating, showing base metal or underplate.	-	Х	Х	-
Stained plating.	-	Х	Х	-
Any blister on plating.	-	Х	-	Х



No. 2053400

ISSUE 2

6.4 SOLDER-PLATING

The following shall be looked for in particular and shall be deemed cause for rejection:	Functional		Non-Functional	
	Accepted	Rejected	Accepted	Rejected
Incorrect distribution of solder alloy.	-	Х	N/A	N/A
Incomplete covering or dewetting.	-	Х	N/A	N/A
Oxidation of plating.	X(1)	-	N/A	N/A
Solder alloy with granular aspect.	X(1)	-	N/A	N/A
Porosity of solder alloy.	X(1)	-	N/A	N/A

NOTES: 1. If solderability test, as per applicable Generic Specification, is acceptable.

6.5 **OTHER DEFECTS**

The following shall be looked for in	Functional		Non-Functional	
particular:	Accepted	Rejected	Accepted	Rejected
• Crack on crimp eyelets showing the edge of the back shell hole.	-	Х	N/A	N/A
 More than three cracks on crimp eyelets of shells. 	-	Х	N/A	N/A
Asymmetry of shell eyelet crimp.	Х	-	N/A	N/A
 Any burr in a groove containing a sealing gasket. 	-	Х	X	-
 Dirty threads. (Accept if dirt removed after application of the specified cleaning process. Otherwise not admissible for re- submission at any time). 	-	Х	-	X
• Deformation or dents on threads.	-	Х	N/A	N/A



No. 2053400

ISSUE 2

7 <u>COMPLETE ASSEMBLIES</u>

All defects described in the preceding paragraphs of this specification are also applicable to complete assemblies.

The following shall be looked for in		Functional		Non-Functional	
	rticular and shall be deemed cause rejection:	Accepted	Rejected	Accepted	Rejected
•	Illegible or incomplete marking.	N/A	N/A	-	Х
•	Incorrect positioning of marking.	N/A	N/A	Х	
•	Faulty marking.	N/A	N/A	-	Х
•	Missing positioning or indicator mark.	N/A	N/A	-	Х
•	Wrong polarisation of insert into housing (circular connectors).	N/A	N/A	-	Х
•	Polarisation out of PID tolerances.	N/A	N/A	-	Х
•	Potting not adhering to insert or shell.	-	Х	Х	-
•	Contact solder pots not facing the same direction (within 15°).	N/A	N/A	-	Х
•	Insert play within shell >0.25mm (for D*M/D*MA types only).	-	Х	Х	N/A