



RADIATION TEST SUMMARY

PART TYPE : IRFY9130


DESCRIPTION : P-CHANNEL POWER MOSFET

REPORT NO. : RD 249

PARAMETERS PLOTTED :

VGS(th)
RDSon

NOTE : The results for the remaining parameters showed no significant change and hence plots were not considered necessary.




Dose (kRad)	Control (mV)	Mean (mV)	Max (mV)	Min (mV)	Lower Limit (mV)	Upper Limit (mV)	Std.Dev.
Initial	2838.0	2829.2	2844.9	2807.8	2000	4000	16.42
0	2838.4	2827.7	2841.6	2806.8	2000	4000	15.53
5	2832.8	3265.5	3290.9	3231.1	2000	4000	25.22
10	2829.9	3649.9	3698.9	3591.7	2000	4000	45.97
15	2826.4	4023.0	4090.0	3944.6	2000	4000	62.75
20	2828.2	4378.4	4464.3	4275.5	2000	4000	82.21
50	2824.7	6304.1	6474.5	6113.6	2000	4000	159.90
End Point	2833.8	6253.0	6409.7	6045.1	2000	4000	156.69
Anneal	2841.6	5959.6	6091.3	5798.9	2000	4000	149.39

Note : Results for both control samples (biased and unbiased) similar therefore average plotted.

Lot size for statistics : 4 devices

RD 249 Date code 9729



Dose (kRad)	Control (Ohms)	Mean (Ohms)	Max (Ohms)	Min (Ohms)	Upper Limit (Ohms)	Lower Limit (Ohms)	Std.Dev.
Initial	0.214	0.215	0.220	0.211	0.310	-	0.00
0	0.223	0.221	0.229	0.215	0.310	-	0.01
5	0.216	0.211	0.216	0.204	0.310	-	0.01
10	0.218	0.217	0.222	0.209	0.310	-	0.01
15	0.221	0.224	0.230	0.215	0.310	-	0.01
20	0.220	0.228	0.233	0.219	0.310	-	0.01
50	0.221	0.291	0.301	0.267	0.310	-	0.02
End Point	0.215	0.317	0.332	0.299	0.310	-	0.01
Anneal	0.212	0.311	0.333	0.297	0.310	-	0.02

Note : Results for both control samples (biased and unbiased) similar therefore average plotted.

ENVISAT-1

RIR 79605

RD249

IRRADIATION TEST PLAN NO.

PO-PL-IGG-PL-0026

Issue No. 1

Date: OCTOBER 1995

Page: 1/4

Rev. NA

Date: NA

Component No. POIG003002B 3	Component Designation: TRANSISTOR, MOSFET, P-CHANNEL, POWER TYPE IRFY9130 4	Irradiation Spec No. NA Iss. Rev. 5
-----------------------------------	--	--

Specifications Generic ESA/SCC 5000 Iss. 7 Rev. B Detail PO-PS-IGG-PL-0030 Iss. 3 6	Acceptance Evaluation Element — Diffusion — Lot <u>X</u> 7	Electrical Measurements In-situ — Remote <u>X</u> 8	Project/Programme ENVISAT-1 9
--	--	--	-------------------------------------

Manufacturer: Name: Int. Rectifier Address: Hurst Green, Oxted Surrey, England 10	Test Facility: Name: ERA Address: LEATHERHEAD, SURREY ENGLAND 11	Originator: IGG CT Name: S THACKER 12
---	---	---

Radiation Source COBALT 60 13	Sample Size: 4 Control Device: 1 (Each Test) 14	Exposure Single — Multiple <u>X</u> 15	Annealing Test YES <u>X</u> NO — 16	Radiation Level: See Below 17
-------------------------------------	---	---	---	-------------------------------------

Single Exposure Dose [Krad(Si)] Dose Rate [rad(Si)/s] Exposure Time Not applicable 18	Multiple Exposure: Irradiation Steps Dose [Krad(Si)] Dose Rate [rad(Si)/s] Exposure Time(s) 19	In accordance with the applicable Appendix to this Plan for each test.
--	---	--

Bias Requirements: During and after Exposure (for remote Electrical Measurements): YES

Bias Conditions:

Test Circuits: The Electrical Bias circuit is given in Figure 1 in the applicable Appendix to this Plan.

Shielding:

Shielding is required to minimize dose enhancement effects caused by low energy, scattered radiation. The test units shall be enclosed in a Pb/Al container of Pb 1.5mm minimum, surrounding on inner shield of 0.7 to 1.0mm Al.
20

Irradiation Test Sequence (applied for each radiation test per the applicable Appendix to this plan).
21

Test Step	Description	Requirements
1	Irradiation Test Samples Selection	Quantity 5 devices shall be selected from the lot delivered to IGG.
2	Serialisation	Serialisation - (if the devices are not already serialised) Test units shall be serialised 1 to 4 and the control unit shall be 5.
3	Initial Electrical Measurements (at IGG)	Per Table A herein - (Read-and-Record) - on all 5 parts at IGG. (See Remarks 1 and 2).
4	Initial Electrical Measurements (at ERA)	Per Table A herein - (Read-and-Record) - on all 5 parts at ERA. (See Remarks 1 and 2).
5	Set-up of Test	Verify Bias Circuit and Voltages (In-situ) for 4 test units.

Irradiation Test Sequence (Cont.)

Test Step	Description	Requirements
6	Irradiation Exposure	Verify radiation dose rate and position in the chamber to achieve required dose. Verify and witness duration of exposure to achieve required dose.
7	Intermediate Electrical Measurement (at ERA)	Bias to be maintained until test is performed. Test per Table A herein - (Read-and-Record) - on all 5 parts. Test to be performed immediately upon removal from chamber (less than 10 mins interval). Upon completion of test 4 test units shall be replaced in bias circuit and returned to chamber. Maximum interval between two consecutive exposures to be 30 mins. (See Remark 2).
8 to 7 + 3n	Repeat Set-up/Exposure/Test sequence upto a Final Total Dose as per the applicable Appendix	Repeat Steps 5, 6, 7 for a total of n cycles (see applicable Appendix). (See Remark 3)
8 + 3n	End Point Electrical Measurements (at IGG)	Per Table A herein - (Read-and-Record) - on all 5 parts at IGG. (See Remarks 2 and 4).
9 + 3n	Annealing	Bias shall be maintained during Annealing for 4 test units. Annealing shall be at room temperature for 168 hours.
10 + 3n	Final Electrical Measurements (at IGG)	Per Table A herein - (Read-and-Record) - on all 5 parts at IGG (See Remark 2).
11 + 3n	Total Dose Irradiation Test Report	ESA/SCC No. 22900

Remarks

1. The initial electrical measurements performed at IGG (Test Step 3) shall be performed within 24 hours of the initial electrical measurements at ERA (Test Step 4).
2. All electrical testing shall be performed on the same set of equipment in order to achieve correlation of results both at IGG and ERA. All results plus details of any failures shall be advised to Project.
3. The set-up/exposure/test sequence shall be stopped for any device that exhibits repeated functional failure.
4. The End Point electrical measurements (Test Step 8 + 3n) performed at IGG shall be performed within 24 hours of the last electrical measurement at ERA (Test Step 7 + 3n).

TABLE A - ELECTRICAL MEASUREMENTS AT ROOM TEMPERATURE - $T_{amb} = +25 \pm 5^{\circ}C$ BEFORE, AT INTERMEDIATE POINTS, AND ON COMPLETION OF IRRADIATION.

NO.	CHARACTERISTICS	SYMBOL	MIL-STD-750 TEST METHOD	TEST CONDITIONS	LIMITS		UNIT
					MIN.	MAX.	
1	Breakdown Voltage Drain to Source	BV_{DSS}	3407 Bias Cond. C	$I_D = -0.25mA_{dc}$ $V_{GS} = 0$	-100	-	Vdc
2	Gate Threshold Voltage	$V_{GS(th)}$	3403	$V_{DS} = V_{GS}$ $I_D = -1mA_{dc}$	-2.0	-4.0	Vdc
3	Gate Current	I_{GSS}	3411 Bias Cond. C	$V_{GS} = -20V_{dc}$ $V_{DS} = 0$	-	-100	nAdc
4	Drain Current	I_{DSS}	3413 Bias Cond C	$V_{DS} = -100V_{dc}$ $V_{GS} = 0$	-	-0.25	mAdc
5	Drain Source ON Resistance	$r_{DS(ON)}$	3421	$V_{GS} = -10V_{dc}$ $I_D = -6.5A_{dc}$ (Notes 2 and 3)	-	0.31	Ω

NOTES

- The limits specified in this Table only apply to the first intermediate electrical measurements at dose 5Krad(Si). For all other intermediate, end point and final electrical measurements, these limits shall not apply but the tests shall be performed and the result recorded for information and characterisation purposes.

Parametric failures to the limits given in this Table could possibly occur at any irradiation level greater than 5Krad(Si).
- Pulsed: Pulse Width $\leq 300\mu S$, Duty Cycle $\leq 2\%$.
- Measured within 2mm of case.

ENVISAT-1

IRRADIATION TEST PLAN NO.

PO-PL-IGG-PL-0026

Issue No. 1

Date: OCTOBER 1995

Page: 4/4

Rev NA

Date: NA

APPENDIX: 1

COMPONENT TYPE: IRFY9130

This appendix defines the specific radiation test requirements applicable to the following ENVISAT-1 user(s):-

USER CODE	USER COMMENT
MPIDGA	Ref. PO-DAS-1365/95


The following specific requirements shall apply:-

a) MULTIPLE EXPOSURE/IRRADIATION STEPS:

Irradiation Steps (n)	1	2	3	4	5
Dose [Krad(Si)]	5	5	5	5	30
Accumulated Dose[Krad(Si)]	5	10	15	20	50
Dose Rate [rad(Si)/s] (See note)	3	3	3	3	3
Exposure Time(s) (See note)	1667	1667	1667	1667	10000

Note: The dose rates and exposure times given are nominal conditions and may be adjusted during irradiation testing to achieve convenient test points. The actual dose rate shall not exceed 3rad(Si)/s. The dose rates and exposure times used during the testing shall be recorded for each test step.

b) ELECTRICAL BIAS CIRCUIT FOR IRRADIATION TESTING:-



NOTES: i) Bias conditions $V_{GS} = -10Vdc$, $V_D = -30Vdc$

ii) $R = 300\Omega \pm 1\%$ to give $I_D = -100mAdc$

	89	91	92	93	94	95
1.1 [V]	130.1	131.0	131.1	124.3	130.6	131.6
2.1 [mV]	2833.8	2842.1	2807.8	2844.9	2825.4	2838.7
3.1 [nA]	1.0	1.1	1.1	1.1	1.1	1.2
4.1 [nA]	1.0	1.1	1.2	1.1	1.1	1.2
5.1 [uA]	0	0	1	0	0	0
6.1 [Ohm]	0.213	0.214	0.214	0.220	0.214	0.21

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
RD249_IRFY9130_INIT_EMS@_ERA / V1.0 21st Dec 95 SMR

=====
Results file : RD249_IRFY9130_INIT_EMS@_ERA from: 12.11.97 / 14:11:38
Operator : PAUL RUSSELL
Part number : IRFY9130
Lot number : RD249
Order number : D/C 9729
Vendor : IR
: CONTROLS: 89 (UNBIASED), 91 (BIASED) ; RAD 92-95
: INITIAL EMS @ ERA
: IRFY9130 PO-PL-IGG-PL-0026 ISS 1 / V1.0 21st Dec 95 SMR
=====

Test steps

1. -V(BR)DSS	100.0	...	700.0	V
2. VGS	2000.0	...	4000.0	mV
3. IGSS (FWD)	(0.0)...		100.0	nA
4. IGSS (REV)	(0.0)...		100.0	nA
5. IDSS	(0)...		250	uA
6. RDS on	(0.000)...		0.310	Ohm

	89	91	92	93	94	95
1.1 [V]	130.0	130.9	131.1	124.5	130.4	131.7
2.1 [mV]	2831.9	2844.8	2806.8	2841.6	2825.4	2837.1
3.1 [nA]	2.0	2.0	2.1	2.0	2.0	2.0
4.1 [nA]	1.9	1.9	1.9	1.9	1.9	1.9
5.1 [uA]	0	0	1	0	0	0
6.1 [Ohm]	0.212	0.233	0.215	0.222	0.216	0.229

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
RD249_IRFY9130_EMS_@_5_KRAD / V1.0 21st Dec 95 SMR

=====
Results file : RD249_IRFY9130_EMS_@_5_KRAD from: 13.11.97 / 10:14:51
Operator : PAUL RUSSELL
Part number : IRFY9130
Lot number : RD249
Order number :
Vendor :
:
: EMS @ 5 KRAD
:
=====

Test steps

1. -V(BR)DSS	100.0	...	700.0	V
2. VGS	2000.0	...	4000.0	mV
3. IGSS (FWD)	(0.0)...		100.0	nA
4. IGSS (REV)	(0.0)...		100.0	nA
5. IDSS	(0)...		250	uA
6. RDS on	(0.000)...		0.310	Ohm

	89	91	92	93	94	95
1.1 [V]	129.9	132.0	130.0	123.9	130.3	131.3
2.1 [mV]	2836.9	2828.6	3231.1	3265.6	3274.4	3290.9
3.1 [nA]	1.4	1.5	1.5	1.5	1.5	1.5
4.1 [nA]	1.4	1.5	1.4	1.4	1.4	1.4
5.1 [uA]	0	0	1	1	1	1
6.1 [Ohm]	0.209	0.223	0.204	0.216	0.212	0.212

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
RD249_IRFY9130_EMS_@_10_KRAD / V1.0 21st Dec 95 SMR

=====
Results file : RD249_IRFY9130_EMS_@_10_KRAD from: 13.11.97 / 10:21:13
Operator : PAUL RUSSELL
Part number : IRFY9130
Lot number : RD249
Order number :
Vendor :
: EMS @ 10 KRAD
:

Test steps

1. -V(BR)DSS	100.0	...	700.0	V
2. VGS	2000.0	...	4000.0	mV
3. IGSS (FWD)	(0.0)	...	100.0	nA
4. IGSS (REV)	(0.0)	...	100.0	nA
5. IDSS	(0)	...	250	uA
6. RDS on	(0.000)	...	0.310	Ohm

8.

	89	91	92	93	94	95
1.1 [V]	130.0	132.3	130.0	124.1	130.3	131.4
2.1 [mV]	2836.5	2823.2	3591.7	3638.6	3670.5	3698.9
3.1 [nA]	1.8	1.6	1.6	1.6	1.6	1.6
4.1 [nA]	1.5	1.5	1.5	1.5	1.5	1.5
5.1 [uA]	0	0	2	2	2	1
6.1 [Ohm]	0.210	0.228	0.209	0.222	0.220	0.218

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
RD249_IRFY9130_EMS_@_15_KRAD / V1.0 21st Dec 95 SMR

```

=====
Results file   : RD249_IRFY9130_EMS_@_15_KRAD   from: 13.11.97 / 10:51:10
Operator      : PAUL RUSSELL
Part number   : IRFY9130
Lot number    : RD249
Order number  :
Vendor        :
              :
              : EMS @ 15 KRAD
              :
=====

```

Test steps

1.	-V(BR)DSS	100.0	...	700.0	V
2.	VGS	2000.0	...	4000.0	mV
3.	IGSS (FWD)	(0.0)	...	100.0	nA
4.	IGSS (REV)	(0.0)	...	100.0	nA
5.	IDSS	(0)	...	250	uA
6.	RDS on	(0.000)	...	0.310	Ohm

	89	91	92	93	94	95
1.1 [V]	130.2	132.6	130.5	124.2	130.3	131.7
2.1 [mV]	2835.0	2817.7	3944.6	4005.1 F	4052.3 F	4090.0 F
3.1 [nA]	1.7	1.8	1.7	1.7	1.7	1.8
4.1 [nA]	1.6	1.7	1.6	1.6	1.6	1.6
5.1 [uA]	0	0	2	2	2	2
6.1 [Ohm]	0.211	0.230	0.215	0.230	0.226	0.224

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
 RD249_IRFY9130_EMS_@_20_KRAD / V1.0 21st Dec 95 SMR

```
=====
Results file   : RD249_IRFY9130_EMS_@_20_KRAD   from: 13.11.97 / 11:21:26
Operator      : PAUL RUSSELL
Part number   : IRFY9130
Lot number    : RD249
Order number  :
Vendor       :
              :
              : EMS @ 20 KRAD
              :
```

Test steps

1. -V(BR)DSS	100.0	...	700.0	V
2. VGS	2000.0	...	4000.0	mV
3. IGSS (FWD)	(0.0)...		100.0	nA
4. IGSS (REV)	(0.0)...		100.0	nA
5. IDSS	(0)...		250	uA
6. RDS on	(0.000)...		0.310	Ohm

	89	91	92	93	94	95
1.1 [V]	130.0	132.5	130.1	124.5	130.4	131.5
2.1 [mV]	2835.4	2820.9	4275.5	4353.9	4419.7	4464.3
3.1 [nA]	1.7	1.8	1.7	1.7	1.8	1.8
4.1 [nA]	1.6	1.7	1.7	1.6	1.6	1.6
5.1 [uA]	0	0	3	3	3	2
6.1 [Ohm]	0.211	0.229	0.219	0.233	0.230	0.230

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
 RD249_IRFY9130_EMS @ 50_KRAD / V1.0 21st Dec 95 SMR

```

=====
Results file   : RD249_IRFY9130_EMS @ 50_KRAD   from: 13.11.97 / 13:40:19
Operator      : PAUL RUSSELL
Part number   : IRFY9130
Lot number    : RD249
Order number  :
Vendor       :
              :
              : EMS @ 50 KRAD
              :
=====
  
```

Test steps

```

=====
1. -V(BR)DSS           100.0   ...   700.0   V
2. V6S                2000.0  ...  4000.0  mV
3. IGSS (FWD)         (  0.0  )...   100.0  nA
4. IGSS (REV)         (  0.0  )...   100.0  nA
5. IDSS                (  0    )...   250    uA
6. RDS on              ( 0.000 )...   0.310  Ohm
=====
  
```

	89	91	92	93	94	95
1.1 [V]	130.3	132.5	130.1	124.2	130.6	131.7
2.1 [mV]	2831.6	2817.7	6113.6	6239.4	6388.9	6474.5
3.1 [nA]	1.9	1.9	2.0	2.0	2.0	2.0
4.1 [nA]	1.8	1.8	1.8	1.8	1.8	1.8
5.1 [uA]	0	0	4	6	5	5
6.1 [Ohm]	0.213	0.230	0.267	0.301	0.297	0.300

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
RD249_IRFY9130_END_POINT_EMS / V1.0 21st Dec 95 SMR

=====
Results file : RD249_IRFY9130_END_POINT_EMS from: 14.11.97 / 13:29:02
Operator : PAUL RUSSELL
Part number : IRFY9130
Lot number : RD249
Order number :
Vendor :
: END POINT EMS
:

Test steps

1. -V(BR)DSS	100.0	...	700.0	V
2. VGS	2000.0	...	4000.0	mV
3. IGSS (FWD)	(0.0)	...	100.0	nA
4. IGSS (REV)	(0.0)	...	100.0	nA
5. IDSS	(0)	...	250	uA
6. RDS on	(0.000)	...	0.310	Ohm

	89	91	92	93	94	95
1.1 [V]	130.3	131.4	131.5	125.2	130.8	131.9
2.1 [mV]	2826.8	2840.8	5045.1 F	5230.8 F	6326.4 F	6409.7 F
3.1 [nA]	1.6	1.6	1.6	1.6	1.7	1.7
4.1 [nA]	1.5	1.5	1.5	1.6	1.6	1.6
5.1 [uA]	0	0	7	7	5	5
6.1 [Ohm]	0.215	0.215	0.299	0.332F	0.317F	0.321F

SZ-TESTSYSTEME Statistics 03 Vers. 2.15 for TA07F
 RD249_IRFY9130_FINAL_EMS / V1.0 21st Dec 95 SMR

```
=====
Results file   : RD249_IRFY9130_FINAL_EMS   from: 21.11.97 / 10:10:47
Operator      : PAUL RUSSELL
Part number   : IRFY9130
Lot number    : RD249
Order number  : D/C 9729
Vendor        : IR
               : CONTROLS: 89 (UNBIASED), 91 (BIASED) ; RAD 92-95
               : FINAL EMS
               : IRFY9130 PO-PL-IGG-PL-0026 ISS 1 / V1.0 21st Dec 95 SMR
=====
```

Test steps

```
-----
1. -V(BR)DSS           100.0   ...   700.0   V
2. VGS                 2000.0  ...  4000.0  mV
3. IGSS (FWD)         (  0.0  )...  100.0   nA
4. IGSS (REV)         (  0.0  )...  100.0   nA
5. IDSS                (  0    )...   250    uA
6. RDS on              ( 0.000 )...   0.310  Ohm
-----
```


	89	91	92	93	94	95
1.1 [V]	130.2	131.1	131.3	124.5	130.6	131.8
2.1 [mV]	2836.3	2846.8	5798.9 F	5865.9 F	6082.1 F	6091.3 F
3.1 [nA]	1.5	1.5	1.4	1.4	1.5	1.4
4.1 [nA]	1.4	1.4	1.4	1.4	1.4	1.4
5.1 [uA]	0	0	5	4	4	3
6.1 [Ohm]	0.212	0.212	0.313F	0.333F	0.297	0.299

I G G
Component
Technology

RECEIVING INSPECTION RECORD

RIR No: 79605

Section 1 Goods Inwards

Date	15Sep1997	Priority	19971231
Supplier	INR/G INTERNATIONAL RECTIFIER G.B. Ltd.	Manu	INR/U INTERNATIONAL RECTIFIER
Part Type	TRANSISTOR IRFY9130	Value	IRFY9130CSCS
Spec No/Option	MIL-PRF-19500 IRFY9130CSCS	Issue	K - - 01
PO No	CT12520 item 4	PO Qty	36 FLIGHT
		Adv Qty	8

Section 2 Project Authorisation

Project/PLIN	000800 / 109907
SAR No	N/A
Part Family	TRANSISTOR

Section 3 Results

WAR No		Date Codes	9729	Act Qty	8
Related RIR Nos		Qty Pass	8	Qty Rej	
Action	Reference	N C R		LOT QTY	
Travel Visual	100%	8			18-9-97 8 (IGG 108 CT)
Visual Inspection	100%				
Solderability	-				
Data Review	100%				
Electrical Measurements	100%				
D P A	3				
Radiation	RD 249 100% .4+2	8	-		806 (IGG 2 CT)
i.a.w. Test Plan PO-PL-IGG-PL-0026/1 App.1					

Section 4 Disposition

Reference	Qty	Authorisation	Date
Project Store			
Reject-Credit/Replacement			
Scrap Store			
D P A (Report No)			
VOQ/Lot Acceptance			
Quarantine (Category)			

Section 6 Stores

Signed..... Date.....



SERIAL NUMBER CHECKLIST

KEY TO CODES USED ON THIS LIST

RIR 79605

0 = DELIVERED TO IGG
 DPA = IGG DPA SAMPLE
 RM = REJECT AT MANUFACTURER
 NCR = REJECT AT IGG

L3E
 L3D
 L2
 INSPECTION STAMP

= LAT3 ELECTRICAL MEASUREMENT
 = LAT3 DESTRICT
 = LAT 2
 = S/NO'S DELIVERED TO USER

START No. 001

1	2	3	4	5	6	7	8	9	10
11	12	13	14	15	16	17	18	19	20
21	22	23	24	25	26	27	28	29	30
31	32	33	34	35	36	37	38	39	40
41	42	43	44	45	46	47	48	49	50
51	52	53	54	55	56	57	58	59	60
61	62	63	64	65	66	67	68	69	70
71	72	73	74	75	76	77	78	79	80
81	82	83	84	85	86	87	88	89	90
91	92	93	94	95	96	97	98	99	00



TRAVEL VISUAL INSPECTION

RIR No. 79605

TASK: 0800

PART TYPE: TRANSISTOR

ACTUAL PART MARKING ^(MANU)_{LOGO} BeO IRFY9130CSCS Δ 9729 #

DATE CODE/LOT IDENTITY: 9729

PACKAGE MARKING: INTERNATIONAL RECTIFIER IRFY9130CSCS # DC 9729 BeO

LEAD FINISH: N/A PART CONDITION: N/A PACKAGE CONDITION: SAT

COMMENTS: YES/NO MECHANICAL DIMENSIONS: N/A

INSPECTED BY: D Crocker DATE: 18-9-97

COMMENTS/OBSERVATIONS