PROTON IRRADIATION FACILITY PIF and PSI ACCELERATORS

Wojtek Hajdas, Roger Brun – PSI LAP

Outline:

- PSI accelerators, areas, users
- PIF tests sides and operation
- Conducting experiment
- Schedule, exposures and support

LABORATORY FOR ASTROPHYSICS

- Future plans

PSI ACCELERATORS

• Injector I – protons (72 MeV) and heavy ions (120 MeV Z^2/A)

ECR source and polarized proton source radiochemistry (heavy ions), biomedicine, space research PIF

Injector II – protons up to 72 MeV

1st stage before ring cyclotron and isotope production

• Ring Cyclotron – 2 mA protons, energy 600 MeV

Protons for biomedicine and space (PIF) applications Production of pions, muons and cold neutrons 8 pions and muons beamlines in operation

• Synchrotron Light Source – infrared to hard X-rays (1000 μm - 40 keV)

5 beamlines in operation (more under construction) material/environment science, protein crystallography, surface studies

 Cold Neutron Source – high intensity neutrons (E ≈ 0.001 – 10 eV) several instruments and test stations (7 beam pipes, 8 stations)

- RADECS Workshop, 26 May 2005

PSI AND ITS EXPERIMENTAL AREAS







CAST LABORATORY FOR ASTROPHYSICS -

PIF AS USER LAB

FEATURES

- Semi-continuous energy setting
- Wide range of intensities
- Uncomplicated set-up and operation
- User-specific test arrangement
- Realistic proton space environment
- Mono-energetic for radiation tests
- Calibration station for detectors
- Qualification of new technologies

USERS

- ESA/ESTEC and subcontractors
- Space Industry (international)
- CERN and Universities
- Other Industry (neutron-proton)
- Internal PSI (new devices)

PIF LOW ENERGY SITE

- Initial energy: 63 MeV
- Energy range: 6 to 63 MeV
- Max flux (6-63 MeV) < 5.10⁸ p/cm²/sec
- Max beam spot
 - φ **= 90 mm**

PAUL SCHERRER INSTITUT

Beam uniformity

90% in of 50 mm circle





PIF HIGH ENERGY SITE

- **Initial energies:** 250, (100, 60) MeV.
- **Energy range:** 35 - 250 (6-60) MeV.
- Max flux at 250 MeV: \approx 2.5-10⁸ /sec/cm², 1 nA.
- Gauss-form profiles FWHM=6 cm (or flat).
- Max exposure diameter:
 - φ **= 90 mm.**
- **Neutron background:** 10⁻⁴ /proton/cm².







FACILITY OPERATION

- 240 beam hours/year reserved for ESA/ESTEC
- Another 240 hours available for other users
- Low energy side operates monthly during OPTIS weeks 12 times/year including weekends 3x12+60 hours/w
- High energy side available on weekends after Biomed
 20 times/year
 from end of April
 50 hours/week
- 30 beam blocks-tests/year
 20 at Low Energy PIF,
 10 at High Energy PIF
 25 research groups



LABORATORY FOR ASTROPHYSICS

7

- RADECS Workshop, 26 May 2005

EXPERIMENTAL ARRANGEMENT I. mounting, positioning, control

• Mounting:

Sample Holder or by User compatible with HIF, Brookhaven platform, suspension etc.

- Position: XY table
 two step motors
 manual and remote control
- Control:

Degrader for setting energy XY - NI SW, identical for LE, HE











EXPERIMENTAL ARRANGEMENT II. dosimetry

- Ionization Chambers
 - air filled
 - total current readout
- Plastic Detectors
 - known area
 - single proton count
- Wire Chamber
 - beam profiles
 - centering
- (Option Si, Nal(TI), NE213)
- Flux/Dose accuracy about 5%







EXPERIMENTAL ARRANGEMENT III. acquisition

- Software user Friendly !
- Users runs PIF themselves
- Identical Scheme for LE,HE
- Run Flow:
 - 1. Initialise
 - 2. Calibrate
 - 3. Input
 - 4. Verification
 - 5. Run
 - 6. Output

• Important:

Calibration Factors

- RADECS Workshop, 26 May 2005

PIF_DAQ	ļ	. 🗆 🗙
<u>File Devices! Calibration! Input! Run! Output! Help!</u>		
DAQ started 07-08-2002 , 10:44:08		
Output Fille PIF2002_07_08h10m44s08_DAQ.txt		
▼ RUN		
		. 1
Status Running	Run # 1 Material	Si ▼ Verify Inp
TARGET ID Test 0		
Comment Beam setup and calibration		
	Est. time to fin	Ish/s RUN
		On
		Off
Fluence /p/cm2 Dose /	rad 1.354E+1	5m
4.406E+8 4.122E	+1 Cross sect	/cm-1
Eliny Intern2te Deserve	0.000E+0	Pause
8.022E+6 7.505E-	1 Total Dose	/rad
	4.122E+1	Open Deanivaive
5.00E+7		Current/Preset Values
0.00E+0 1.00E+8	Fluence/Dose% Time%	Man Dom King Ja
Flux /cm2/s	100.0- 100.0-	
3.2E+7-	80.0- 80.0-	
ي 2.5E+7-	60.0- 60.0-	Huence /p/cm2 1 /mm
5 2.0E+7-	40.0- 40.0-	
	20.0- 20.0-	Dose /rad Degr. /mm
5.0E+6-	0.0- 💻 0.0- 🖕	<u>19.000272</u> <u>10</u>
9.2E+5-	4.4 0.3	Split Current /uA
0 25 50 75 100 Time /s	,	75360.00



CONDUCTING EXPERIMENT training and radiation safety

- Software and test step-by-step procedure available on web
- **Device exposure training before starting irradiation (15 min)**
- How-to enter and exit experimental area available on web
- Area enter and exit demonstration and training before test (10 min)
- Dosimetry and radiation safety course required for new users ۲
- Course has to be completed before test (ca. 35 min, 3 end-questions)
- All experimental materials (from area) must be checked after irradiation



11

SET UP, EXPOSURE and COSTS

- User has several hours to prepare its experiment
- PIF setup is arranged in accordance to test needs
- Exposure campaign starts with beam setup (1 2 h)
- Dosimetry devices are calibrated (0.5 1 h)
- User test runs are carried out in accordance to schedule
- After exposures all materials are checked for activation
- Activated materials are stored in special magazine
- Beam costs are 500 (650) Euro/hour (min 8 hours, flat rate)
- Penalty for cancelled runs with large PIF pre-work
- For common research projects cost reduction



PERSONNEL, SUPPORT and CONTACTS

- Roger Brun and Wojtek Hajdas run PIF at PSI
- PIF stuff available during setup and first exposures
- Further support on request /
 - on-call immediately
 - SW and PC controlled HW remotely
 - picket availability within 5-30 min
- Cyclotron operators permanent presence
- SU physicist either as picket or after exposures (morning)
- Services available during week working hours:
 - mechanical and electronic workshop
 - central magazine
 - vacuum group, area services, crane operators
- All contact addresses and phones on web (pif.web.psi.ch)



FUTURE DEVELOPMENTS all in one - PROSCAN

- Construction in accordance to schedule
- First protons extracted on 1st April 05
- Cyclotron commissioning in progress
- New PIF commissioning end of 2006
- PIF PROSCAN operation from 2007







